GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

AUCTION SALE OF NUMERICAL MATERIALS OF THE CENTRAL STORES.

Abstract Notification dated 23rd May 1938.

Attention of the public is invited to the detailed Notification relating to the above, published in the *Mysore Gazette*, dated 2nd June 1938, Part VI, pages 894-900 for information. The materials noted therein will be sold by public auction on 20th June 1938 between 9 A.M. and 12 NOON.

Abstract Notification dated 24th May 1938.

The attention of firms dealing in electrical machinery is invited to this Office Gazette Notification No. G. N. 24, dated 24th May 1938, published on page 901 of Part VI of the *Mysore Gazette*, dated 2nd June 1938.

S. G. FORBES,
Chief Electrical Engineer.

OFFICE OF THE SUPERINTENDING ENGINEER, ELECTRICAL DEPARTMENT, BANGALORE.

Notification dated 1st June 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, up to 1 P.M. on the 24th June 1938 for constructing the following Electrical Buildings at Krishnarajanagar, Gaudigere and Hunsur Towns. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of December 1938. Tenders may be submitted in full or in parts.

BUILDINGS AT KRISHNARAJNAGAR.

1. Combined Station, Office and Stores.
2. Senior Operator's Quarters.
3. Two Blocks of Operators' quarters.
4. One and a half Blocks of Linemen's quarters.
5. Four Blocks of Latrines.

BUILDINGS AT GAUDIGERE.

1. One Block of Linemen's quarters.
2. One Block of Latrine.

BUILDINGS AT HUNSUR.

1. Combined Station, Office and Stores.
2. One Block of Operator's quarters.
3. One and a half Blocks of Linemen's quarters.
4. Two Blocks of Latrines.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 for buildings at Krishnarajanagar, Rs. 150 for buildings at Gaudigere and Rs. 600 for buildings at Hunsur, in cash or Government Promissory notes, as earnest money, and be superscribed "Tender for constructing Electrical Buildings at Krishnarajanagar, Gaudigere and Hunsur Towns", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be pasted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Electrical Engineer, will be final and leagally binding.

a b

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during execution will not be paid for separately but should be borne by the Contractor.

Abstract estimate for constructing a Combined Building for Station, Office and Stores at Krishnarajnagar.

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement, including watering and ramming, etc.	C.yd.	0 3 3	67	
2	Stone jelly concrete in lime mortar	,,	0 3 3	592	
3	Size stone in lime mortar foundation and basement with bond stones	C.ft.	0 5 6	1,262	
4	Burnt brick in lime mortar superstructure	,,	0 4 3	2,146	
5	Stone slabs 6" thick, exposed parts dressed and fixed complete	S.ft.	0 10 6	150	
6	Stone slabs 6" thick, roughly dressed and set in lime	,,	0 9 0	155	
7	Chunam plastering ½" thick	Sqr.	3 0 0	43·00	
8	Cement pointing with thread lines	,,	3 0 0	2·50	
9	White and colour washing, 2 coats	,,	0 4 3	45·50	
10	Flooring with cement concrete 1½" thick over 4" thick lime concrete with ½" thick cement, plastered and coloured red	,,	28 0 0	9·59	
11	Burnt brick in lime for pillars 1½'×1½' with base and capitals as per design with bond stones at intervals 3 to 4 ft. with lime plastering, white-washing, etc., complete	No.	10 0 0	6	
12	Terrace filled in with brick in surki mortar with wedge-shaped R.C. joists with 3" to 6" thick surki concrete, 2 courses of flat tiles and surface and ceiling lime plastered, ½" thick, etc., complete, as per detail sketch	Sqr.	60 0 0	14·73	
13	Parapet wall built of brick in chunam and lime plastered 9"×1'–9" with necessary pillasters complete as per design	R.ft.	1 4 0	201	
14	Rolled steel girders hoisted and fixed complete, including pointing (Tata's tested)	Cwt.	14 0 0	28·28	
15	Teakwood doors panelled 1¼" thick shutters, frames 3"×5" with fixtures, etc., complete as per drawing	S.ft.	2 0 0	126	
16	Teakwood windows glazed 1¼" thick shutters frames 3"×4" with ¾" diameter iron bars with fixtures complete, as per drawing	,,	2 4 0	123	
17	Teakwood ventilators glazed 1" thick shutters frames 3"×3" with iron bars ¾" diam. complete.	,,	1 4 0	68	
18	R.C. jelly work fixed complete, as per design	,,	2 4 0	125	
19	Teakwood partition 3"×4" frame work and ¾" thick planks with tongue and groove joints with fittings complete including 2 coats of wood oiling	,,	1 4 0	225	
20	Boxing girders with brick in cement and lime plastering complete with necessary wire-netting for binding	R.ft.	0 12 0	45	
21	Providing and fixing 3" sqr. size rain-water down pipes, made of 22 B.W.G. plain galvanized iron sheeting complete including painting	,,	0 8 0	60	
22	Silicate painting, 2 coats	Sqr.	5 0 0	4·43	
23	Providing and fixing 2" G.I. pipe for flag-staff and painting	L.S.			
24	Cement concrete with centering, including plastering at side and bottom	C.ft.	1 0 0	36	
25	Printing letters 6"×4" for the name of the building on the parapet wall with cement and painted complete	L.S.			
26	Providing and fixing slabs, 4" thick on 3" lime concrete, below rain-water pipes 2'×2'	S.ft.	0 8 0	40	

Abstract estimate for constructing a Senior Operator's Quarters at Krishnarajnagar.

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
1	Earthwork excavation in ordinary soil and filling in basement including watering and ramming.	C.yd.	0 3 3	53	
2	Stone jelly in mortar foundation	C.ft.	0 3 3	442	
3	Stone in clay foundation and basement with bond stones	,,	0 3 6	1,383	
4	Burnt brick in clay superstructure	,,	0 3 6	1,911	
5	Burnt brick in mortar superstructure	,,	0 4 3	535	
6	Stone slabs 6" thick and fixed in lime	S.ft.	0 9 0	164	
7	Stone slabs 3" thick fixed in lime	,,	0 8 0	28	
8	Pointing with cement mortar, with thread lines	Sqr.	3 8 0	2·40	
9	Plastering with mortar	,,	3 0 0	49·05	
10	White and colour washing, 2 coats	,,	0 4 3	51·45	
11	Plain cornice, 9" deep	R.ft.	0 7 0	52	
12	Burnt brick in mortar parapet walls 9" thick and 1½ to 2 ft. high, complete	,,	1 4 0	50	
13	Flooring with 1" cement concrete on a bed of 3" lime mortar concrete and ½" thick cement plaster	Sqr.	28 0 0	8·40	
14	Roofing with first class Mangalore tiles on T.W. reepers 2"×1" including wood oiling to reepers.	,,	28 0 0	12·03	
15	Ridge tiles set in mortar and cement pointed	R.ft.	0 8 0	73	
16	Brick nogged terrace filled in with brick in surki mortar complete with wedge R.C. joists with surki concrete, 2 coats of flat tiles, surface and ceiling plastered	Sqr.	60 0 0	2·89	
17	Teakwood work with wood oiling, etc., complete	C.ft.	4 8 0	62·73	
18	Plain teakwood eave-board, 9"×¾" fixed complete	R.ft.	0 9 0	164	
19	Doors with teakwood frames and honney wood batten shutters 1" thick including fixtures complete	S.ft.	1 2 0	163	
20	Windows with teakwood frames and honney wood batten shutters with iron bars, etc., ⅝" dia. with fixtures	,,	1 5 0	110	
21	Teakwood cup-boards with battened shutters 1" thick and T.W. planks for shelves	,,	1 0 0	48	
22	Steel girders fixed complete, including painting (Tata's tested)	,,	14 0 0	4·83	
23	Expanded metal 3"×1½" with ⅛" strands with T.W. frame work fixed complete with doors	,,	0 10 0	111	
24	Chocolate painting, 2 coats	Sqr.	3 8 0	11·84	
25	Ventilating tiles fixed with cement	No.	1 8 0	6	
26	Constructing sinks 3'×3' walls, etc.	,,	5 0 0	2	
27	Stone pestle and mortar fixed, complete	,,	4 0 0	1	
28	Chunam border at rear roof	R.ft.	0 3 0	26	
29	Rain-water down pipes 3" dia. of plain G.I. sheeting, fixed with clamps, etc., complete, including painting	,,	0 6 0	50	
30	Constructing chimney, etc., in Kitchen	L.S.			
31	Levelling the ground	,,			

Abstract estimate for constructing one unit of Double Block of Operator's Quarters at Krishnarajnagar.

Item No.	Description of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	0 3 3	53	
2	Stone jelly concrete in lime mortar	C.ft.	0 3 3	596	
3	Size stone in clay foundation and basement with bond stones	,,	0 3 6	1,031	
4	Burnt brick in clay superstructure	,,	0 3 6	2,097	
5	Do lime do	,,	0 4 3	519	

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
6	Stone slabs 6" thick roughly dressed and fixed in lime	S.ft.	0 9 0	415	
7	Cement pointing with thread lines	Sqr.	3 8 0	1·53	
8	Chunam plastering, 2 coats	„	3 0 0	55·43	
9	White and colour washing, 2 coats	„	0 4 3	56·96	
10	Plain cornice 9" thick as per design	R.ft.	0 7 0	61	
11	Burnt brick in lime parapet wall 9" thick as per design	„	1 4 0	58	
12	Flooring with 1" thick cement concrete over 3" lime concrete with ½" cement plaster on top	Sqr.	22 0 0	8·44	
13	Roofing with first class Mangalore tiles on T.W. reepers 2"×1" including wood oiling to reepers.	„	28 0 0	12·21	
14	Ridge tiles set in mortar and cement pointed	R.ft.	0 8 0	75	
15	Brick nogged terrace filled in with wedge shaped R.C. joists with surki concrete, 2 coats of flat tiles, surface and ceiling plastered	Sqr.	60 0 0	3·70	
16	Plain teakwood eave-boarding 9"×¾" fixed complete	R.ft.	0 9 0	149	
17	Teakwood wrought and put up complete with wood oiling, 2 coats	C.ft.	4 8 0	76·58	
18	Doors with teakwood frames and honney wood battened shutters 1" thick with fixtures, etc., complete	S.ft.	1 2 0	319	
19	Teakwood windows with honney wood battened shutters and iron bars with fixtures, etc., complete	R.ft.	1 5 0	96	
20	Teakwood cup-boards with panelled shutters and T.W. planks for shelves	S.ft.	1 2 0	96	
21	Rolled steel girders fixed complete including painting (Tata's tested)	Cwt.	14 0 0	6·40	
22	Expanded metal 3"×1½" mesh with ⅛" strands with T. W. frame work with doorways, etc., complete	S.ft.	0 10 0	112	
23	Chocolate painting, 2 coats	Sqr.	3 8 0	13·57	
24	Ventilating tiles	No.	1 8 0	8	
25	Constructing sinks complete, with outlet pipes	„	5 0 0	2	
26	Providing and fixing stone mortar and pestle	„	4 0 0	2	
27	Chunam borders at ends of roof	R.ft.	0 4 0	22	
28	Rain-water down pipes 3" dia. of plain galvanized iron sheet fixed with clamps, etc., complete including painting	„	0 6 0	65	
29	Constructing chimney, etc., in the kitchen	No.	20 0 0	2	
30	Levelling ground	L.S.			

Abstract of the Estimate for constructing Line-men's Quarters at Krishnarajnagar.

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement including watering, and ramming	C.yd.	0 3 3	33	
2	Stone jelly in lime mortar concrete for foundation.	C.ft.	0 3 3	287	
3	Size stone in clay foundation and basement with bond stones	„	0 3 6	911	
4	Burnt brick in clay superstructure	„	0 3 6	1,692	
5	Burnt brick in lime mortar superstructure	„	0 4 3	513	
6	Stone slabs 6" thick roughly dressed and set in lime	S.ft.	0 9 0	195	
7	Binding wall 6"×6" of brick in lime mortar and chunam plastered	R.ft.	0 2 6	28	
8	Chunam plastering, 2 coats	Sqr.	3 0 0	45·04	
9	Pointing with cement mortar with thread lines	„	4 0 0	1·45	
10	White and colour washing, 2 coats	„	0 4 3	46·49	
11	Roofing with first class Mangalore tiles on T.W. reepers including wood oiling to reepers	„	28 0 0	14·43	

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
12	Ridge tiles set in mortar and cement pointed	R.ft.	0 8 0	77	
13	Ventilating tiles set in mortar and cement pointed	No.	1 8 0	16	
14	T.W. wrought and put up with 2 coats of wood oiling	C.ft.	4 8 0	52·48	
15	Doors with T.W. frames and honney wood battened shutters 1" thick with fittings, etc., complete	S.ft.	1 2 0	156	
16	Windows with T.W. frames and honney wood battened shutters 1" with iron bars $\frac{5}{8}$" dia. and fittings, etc., complete	,,	1 5 0	60	
17	Chocolate painting, 2 coats	Sqr.	3 8 0	4·62	
18	Constructing sinks in bath rooms	No.	5 0 0	4	
19	Providing stone mortar and pestle	,,	4 0 0	4	
20	Flooring with 3" lime concrete and 1" cement concrete with $\frac{1}{2}$" thick cement plastering on top	Sqr.	22 0 0	7·58	
21	Constructing parapet wall with brick in lime mortar 2' high with Cudappah slab on top with plastering, etc., complete	R.ft.	0 12 0	37	
22	Providing expanded metal trellis work in front verandah including a door in each	S.ft.	0 10 0	241	
23	Levelling ground	L. S.			

N.B.—The details given are for one block only.

Abstract estimate for constructing combined Station, Office and Stores Building at Hunsur Town.

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement	C.yd.	0 3 3	39	
2	Stone jelly in lime concrete foundation	C.ft.	0 4 0	361	
3	Stone in lime foundation and basement including through stones every 6' apart in every course.	,,	0 5 6	869	
4	Burnt brick in clay superstructure	,,	0 3 6	1,298	
5	Do mortar do	,,	0 5 0	144	
6	Stone slabs 6" thick roughly dressed and fixed in mortar	S.ft.	0 13 0	177	
7	Stone slabs 3" thick exposed parts one line dressed and set in mortar	,,	0 12 0	7	
8	Brick in mortar pillars $1\frac{1}{2}$' square and 9'-9" high including stone base and capital and cement plaster $\frac{1}{2}$" thick	Each	8 0 0	4	
9	Chunam plastering, 2 coats	Sqr.	3 8 0	29·00	
10	Cement pointing with thread lines	,,	3 14 0	1·88	
11	White and colour washing, 2 coats	,,	0 14 0	31·00	
12	Brick cornice 6" projection as per design	R.ft.	0 8 0	158	
13	Brick in mortar parapet wall 9" thick as per design.	R.ft.	1 4 0	155	
14	Chunam moulding 6" × $\frac{1}{2}$" alround ventilators	,,	0 2 0	77	
15	Chunam moulding in front wall between pillars	No.	4 0 0	4	
16	Cudappah slab flooring $1\frac{1}{2}$" thick on 3" concrete bed and cement pointed with thread lines	Sqr.	30 0 0	1·94	
17	First class Mangalore tiles flooring 3" lime concrete and cement pointed	,,	30 0 0	4·06	
18	Roofing with Madras terrace 9" thick including plastering, etc., complete	,,	38 0 0	6·75	
19	Steel work fixed complete (Tata's) with two coats of painting	Cwt.	14 0 0	44·00	
20	T.W. doors panelled $1\frac{1}{2}$" thick shutters with fixtures, etc., complete	S.ft.	2 0 0	92	
21	T.W. Glazed windows $1\frac{1}{4}$" thick shutters with iron bars $\frac{5}{8}$" dia. with fixtures, etc., complete	,,	1 12 0	70	
22	T.W. ventilators glazed with iron bars	,,	1 6 0	27	
23	Chocolate painting, 2 coats	Sqr.	3 8 0	12·87	
24	Fixing wire-gauze shutters with T.W. battens and spring hinges, complete	S.ft.	1 6 0	63	
25	Rain-water down G.I. pipes fixed 3" dia.	R.ft.	0 6 0	78	
26	Brick in lime mortar and stone slabs with chunam plastering, etc., complete for brackets	No.	3 0 0	10	
27	Clearing site and levelling the ground, etc.	L.S.			

Abstract estimate for constructing one unit of double block of Operator's Quarters at Hunsur Town.

Item No.	Description of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement including watering and ramming, etc. ..	C.yd.	0 3 3	53	
2	Stone jelly concrete in lime mortar	C.ft.	0 4 0	596	
3	Size stone in clay foundation and basement ..	C.ft.	0 4 3	1,031	
4	Burnt brick in clay superstructure	,,,	0 3 6	2,097	
5	Do in lime do	,,	0 5 0	519	
6	Stone slabs 6″ thick roughly dressed and fixed in lime	S.ft.	0 13 0	415	
7	Cement pointing with thread lines	Sqr.	3 14 0	1·53	
8	Chunam plastering, 2 coats	,,	3 8 0	55·43	
9	White and colour washing, 2 coats	,,	0 5 0	56·96	
10	Plain cornice 9″ thick as per design	R.ft.	0 8 0	61	
11	Burnt brick in lime parapet wall 9″ thick as per design	,,	1 4 0	..	
12	Flooring with 1″ thick cement concrete over 3″ lime concrete with ½″ cement plaster on top ..	Sqr.	28 0 0	8·44	
13	Roofing with first class Mangalore tiles on T. W. reepers 2″×1″ including wood oiling to reepers	,,	30 0 0	12·21	
14	Ridge tiles set in mortar and cement pointed ..	R.ft.	0 8 0	75	
15	Terrace filled with brick in surki mortar with wedge shaped R. C. joists with surki concrete 2 coats of flat tiles, surface and ceiling plastered ..	Sqr.	60 0 0	3·70	
16	Plain teakwood eave-boarding 9″×¾″ fixed complete	R.ft.	0 9 0	149	
17	T. W. wrought and put up comp: with wood oiling 2 coats	C.ft.	5 8 0	76·58	
18	Doors with T. W. frames and honney wood battened shutters 1″ thick with fixtures, etc., complete	S.ft.	1 0 0	319	
19	T. W. windows with honney wood battened shutters and iron bars, with fixtures, etc., complete	S.ft.	1 5 0	96	
20	T. W. cup boards with panelled shutters and T. W. planks for shelves	S.ft.	1 8 0	96	
21	Rolled steel girders complete including painting (Tata's tested)	Cwt.	14 0 0	6·40	
22	Expanded metal 3″×1½″ mesh with ⅛″ strands with T. W. frame work with doorways, etc., complete	S.ft.	1 8 0	96	
23	Chocolate painting, 2 coats	Sqr.	3 8 0	13·57	
24	Ventilating tiles	No.	2 8 0	8	
25	Constructing sinks, complete with outlet pipes ..	No.	5 0 0	2	
26	Providing and fixing stone mortar and pestle ..	No.	8 0 0	2	
27	Chunam borders at ends of roof	R.ft.	0 4 0	22	
28	Rainwater down pipes of 3″ dia. of plain G. I. sheet fixed with clamps, etc., complete including painting	,,	0 8 0	65	
29	Providing and fixing brass or copper handes in bath rooms	No.	15 0 0	2	
30	Constructing Chimney, etc., in kitchen ..	No.	20 0 0	2	
31	Levelling ground	L.S.			

Abstract estimate for constructing Line-men's quarters at Hunsur and Gaudigere Towns.

Serial No.	Description of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement, including watering and ramming, etc. ..	C.yd.	0 3 3	33	
2	Stone jolly in lime concrete for foundation ..	C.ft.	0 4 0	287	
3	Size stone in clay, foundation and basement with bond stones	,,	0 4 3	911	

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
4	Burnt brick in clay superstructure	C.ft.	0 3 6	1,692	
5	Burnt brick in lime mortar, superstructure ..	,,	0 5 0	513	
6	Stone slabs 6" roughly dressed and set in lime ..	S.ft.	0 13 0	195	
7	Binding wall 6" and 6" of burnt brick in lime mortar and chunam plastered	R.ft.	0 4 0	28	
8	Chunam plastering, 2 coats	Sqr.	3 8 0	45.04	
9	Pointing with cement with thread lines ..	Sqr.	3 14 0	1.45	
10	White and colour washing, 2 coats	,,	0 5 0	46.49	
11	Roofing with 1st Class Mangalore tiles on T. R. including wood oiling to reepers	Sqr.	30 0 0	14.43	
12	Ridge tiles set in mortar and cement pointed ..	R.ft.	0 8 0	77	
13	Ventilating tiles set in mortar and cement pointed.	No.	2 12 0	16	
14	Teakwood wrought and put up with wood oiling, 2 coats	C.ft.	5 8 0	52.48	
15	Doors with Teakwood frames and honney wood battened shutters 1" thick with fixtures, etc., complete as per drawing	S.ft.	1 0 0	156	
16	Windows with teakwood frames and honney wood battened shutters 1" thick with iron bars $\frac{5}{8}$" diameter and fixtures, etc., complete as per drawing	S.ft.	1 5 0	60	
17	Chocolate painting 2 coats	Sqr.	3 8 0	4.62	
18	Constructing sinks in bath rooms	No.	5 0 0	4	
19	Providing and fixing stone mortar and pestle ..	No.	8 0 0	4	
20	Flooring with 1" thick cement concrete on 3" lime concrete and $\frac{1}{2}$" cement plaster on top. ..	Sqr.	24 0 0	7.58	
21	Constructing parapet wall plain 9" thick and 2 ft. high, with brick in lime and chunam plastered.	R.ft.	0 14 0	37	
22	Providing and fixing expanded metal with teakwood frame work including doors	S.ft.	0 10 0	241	
23	Levelling ground	L.S.		One Item	

N.B.— The details given are for one block only.

Abstract estimate for constructing one unit of Latrine at Krishnarajanagar.

Serial No.	Description of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	0 3 0	4	
2	Stone in clay foundation and basement with bond stones	C.ft.	0 3 6	130	
3	Burnt brick in lime mortar, superstructure ..	C.ft.	0 4 3	196	
4	Chunam plastering	Sqr.	3 0 0	4.91	
5	Cement pointing with thread lines	,,	4 0 0	0.56	
6	White and colour washing, 2 coats	,,	0 4 3	5.47	
7	Cement plastering $\frac{1}{2}$" thick	,,	10 0 0	0.79	
8	Tar washing, 2 coats	,,	2 0 0	0.63	
9	Flooring with 1" cement concrete and $\frac{1}{2}$" cement plaster over a bed of 3" lime concrete ..	,,	22 0 0	0.38	
10	Fixing outlets and constructing drains, etc. ..	L.S.	10 0 0	1 Item	
11	Providing galvanized iron sheet tubs 12" & 6" of 22 B. W. G. complete with tarring	No.	1 8 0	6	

Abstract estimate for constructing one unit of Latrine at Gaudigere and Hunsur Towns.

Serial No.	Description of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	0 3 3	4	
2	Stone in clay foundation and basement with bond stone	C.ft.	0 4 3	130	

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
3	Burnt brick in lime mortar, superstructure ..	C.ft.	0 3 6	196	
4	Chunam plastering	Sqr.	3 8 0	4.91	
5	Cement pointing with thread lines	,,	3 14 0	0.56	
6	White and colour washing, 2 coats	,,	0 5 0	5.47	
7	Cement plastering ½" thick	,,	10 0 0	0.79	
8	Tar washing 2 coats	,,	2 0 0	0.63	
9	Flooring with 1" cement concrete and ½" cement plaster over a bed of 3" lime concrete ..	,,	24 0 0	0.38	
10	Fixing outlets and constructing drains, etc. ..	L.S.	10 0 0	1 Item	
11	Providing galvanized iron sheet tubs 12"& 6" of 22 B. W. G. complete with tarring	No.	1 8 0	6	

A. C. MUNIRATNA MUDALIAR,
For *Superintending Engineer.*

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

Notification No. G. N. 25, *dated* 11*th June* 1938.

Sealed tenders will be received in the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 2 P.M. on 2nd July 1938, for the supply of the following :—

9200—Nos. " J " bolts made out of ⅜" M. S. rounds bent at right-angles, one arm 6" long with tapering end and threaded to a length of 2½" and the other arm 2" long, the distance between the two arms being 2⅛" (internal), complete with 2 hexagonal nuts per bolt.

N.B.—Dimensional sketch of the " J " bolts required may be obtained on application to the Deputy Chief Electrical Engineer to the Government of Mysore, Bangalore.

2000 of the above have to be delivered f.o.r., Bhadravathi,
2000—f.o.r., Davangere,
1600—f.o.r., Closepot and
3600—f.o.r., Bangalore City or at the C.P.S. Central Stores near Binny Mills, Bangalore City.

The tenderers should quote their rates for deliveries at the respective places above referred to and *on number basis only* (*i.e.*, so much per dozen) and not on weight basis ; and time of delivery should be noted.

The Chief Electrical Engineer reserves to himself the right to refuse the lowest or any tender, whole or part, without assigning any reason therefor.

Withdrawal from the quotation after it is accepted or failure to make the supply within the specified time or according to specifications will entail cancellation of the order and purchase being made at the firm's expense from other sources.

Tenders should be superscribed " Tender for the supply of " J " bolts to be opened at 2 P.M., on 2nd July 1938 ".

S. G. FORBES,
Chief Electrical Engineer.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, MYSORE.

Notification dated 11*th June* 1938.

Sealed tenders for the carting of materials and supply of building materials for one year or until further orders from the date of acceptance, will be received in the Office of the Superintendent, Power and Lighting, Mysore, till 1st July 1938.

Tenders should be addressed to the Superintendent, Power and Lighting, Mysore, and should be sent *in triplicate*, enclosed in sealed covers duly superscribed " *Tenders for carting of materials and supply of building materials* " to be opened on 1st July 1938 ".

The tenders must be accompanied, under separate cover, either by Registered Post, Money Order or personally, by a deposit of Rs. 25 for each or Rs. 50 for the whole, as otherwise the tender will not be considered.

The successful tenderer will be required to sign a contract deed immediately after the acceptance of his tender is communicated to him.

The rates to be tendered should be entered both in figures and in words. When once the tender is accepted, no special rate will be allowed on any representation for special consideration.

Payment will be made on bills prepared and submitted by the contractor in specified printed forms once in every month or if so desired by the contractor, once in a fortnight or even earlier as may be decided by mutual agreement.

If materials are not carted as and when required, the work will be got done through other agency. Similarly if the materials are not supplied as and when required, they will be arranged to be purchased from other sources at the rates prevailing at the time. The extra cost if any, paid or payable, in either case shall be borne by the accepted contractor and shall be debited to his account.